BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Providing Cement Concrete Roads near Anjaneya Temple Shettyhalli, in Ward No-12, Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed Complete as per Specifications.	Cum	420.87	126.36	Rupees One Hundred Twenty Six and Thirty Six Paise Only
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing Complete as per Specifications.	Cum	210.44	4497.12	Rupees Four Thousand Four Hundred Ninety Seven and Twelve Paise Only
3	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams.Complete as per Specifications.	Cum	140.29	6464.88	Rupees Six Thousand Four Hundred Sixty Four and Eighty Eight Paise Only
4	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per Drawing & Technical Specification.Complete as per Specifications.	m	20.00	137.16	Rupees One Hundred Thirty Seven and Sixteen Paise Only
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Complete as per Specifications.	Cum	420.87	94.82	Rupees Ninety Four and Eighty Two Paise Only

Technical Manager(TW-2)
KRIDL, Dasarahalli Zone, Bangalore

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,